



Pickens County Airport Terminal

193 Pickens Airport Rd

Jasper, GA 30143

ADDENDUM #2

7 November 22

The Drawings and Specifications for the above referenced project are hereby clarified and/or amended as follows. Note **ATTACHED** indicates an attachment is included :

SPECIFICATIONS

ITEM 1 : Replace Section 01020 Allowances with Attached.

ITEM 2 : Add Section 08420 Aluminum Curtain Wall Attached.

ITEM 3: Section 09900 Painting.

3.04, B. Painting Schedule EXTERIOR. Revise Para. 5. Revise to read

5. Exterior Wood Soffit & Timber Trusses.

a. Two Coats. Sherwin-Williams "WoodScapes" Exterior Polyurethane Semi-Transparent Stain

3.04 C. Painting Schedule INTERIOR. Revise para. 6 to read.

6. All Interior Hardwood, Timber Trusses stain finish.

a. Two coats. Oil stain.

b. Two coats. Urethane varnish (gloss finish, unless otherwise specified in Section 09999, COLOR SCHEDULE).

c. Sand lightly between coats.

DRAWINGS

ITEM 1 : A2.1 Schedules. Replace Drawing with Attached, 1 Nov 22 : Revise Type M Aluminum Frames to 6" Curtain Wall

ITEM 2 : S0.1 General Notes. Part X, Heavy Timber Framing. C. Materials, 3. "...unless noted otherwise, provide Southern Yellow Pine...." Add Pressure Treated for Timber exposed to Weather, i.e., Exterior Truss between A& D Column Lines, and the Porte Cochere Trusses."

ITEM 3 : S1.2 Roof Framing Plan. Replace Drawing with Attached, 1 Nov 22. Revise Column Line designation.

END OF ADDENDUM